

EVALUARE

Obiect Nr.3. INSTALATIi DE ILUMINAT PUBLIC

Categorie Nr.2. DEMONTARE 7 STALPI

						[ron]
Nr. Crt.	Capitol lucrari Simbol Denumire resursa Observatii Corectii Liste Anexe	U/M	Cantitatea	Pretul unitar a)materiale b)manopera c)utilaj d)transport Total(a+b+c+d)	Valoare	
1	TSA17B2	82 M CUB	14.00000	0.00	0.00	
				40.64	568.96	
	SAP.MAN.GROPI POLIG.MONOBL.PT.LINII EL.PAM.CU UMID			0.00	0.00	
	.NAT.CU SPRIJ.LAT.<1M,ADINC.<2,5M,T.TARE			0.00	0.00	
				40.64	568.96	
2	TSD01B1	82 M CUB	14.00000	0.00	0.00	
				2.45	34.30	
	IMPRASTIEREA CU LOPATA A PAMINT.AFINAT,STRAT UNIFO			0.00	0.00	
	RM 10-30CM.GROS CU SFARIM.BULG.TEREN MIJL.			0.00	0.00	
				2.45	34.30	
3	TSD04B1	82 M CUB	14.00000	0.07	0.98	
				6.00	84.00	
	COMPACTAREA CU MAI.DE MINA A UMPLUT.EXECUT.PE STRA			0.00	0.00	
	T.CU UDAREA FIEC.STRAT DE 10CM GROS.T.COEZIV			0.00	0.00	
				6.07	84.98	
4	W2A16B	99 BUCATA	7.00000	0.00	0.00	
				32.00	224.00	
	STILP PT.ILUMINAT PUBLIC STRADAL DIN TV.OTEL >5M I			19.44	136.08	
	NALTIME, MONTAT CU AUTOMACARA IN FUNDATIE TURNATA			0.00	0.00	
				51.44	360.08	
-----C:01:1.00:DEMONTARE-----						
5	W2F03A	99 BUCATA	7.00000	0.00	0.00	
				6.88	48.16	
	CORP DE ILUMIN.EXT.ECHIPAT CU LAMPI CU LED 70 W MO			0.00	0.00	
	NTAT PE STILP METAL 9 M PLANTAT			0.00	0.00	
				6.88	48.16	
-----C:01:1.00:DEMONTARE-----						
6	AUT1368	82 ORE	4.00000	0.00	0.00	
				0.00	0.00	
	ORA PR MACARA PE PNEURI BR.TELESCOP TELEMAR HT125			120.00	480.00	
	3 SCHIM	\$		0.00	0.00	
				120.00	480.00	
7	TRA01A05	82 TONE	5.00000	0.00	0.00	
				0.00	0.00	
	TRANSPORTUL RUTIER AL MATERIALELOR,SEMIFABRICATELO			0.00	0.00	
	R CU AUTOBASCULANTA PE DIST.= 5 KM.	\$		11.05	55.25	
				11.05	55.25	
Total A:					0.98	
					959.42	
					616.08	
					55.25	
					1,631.73	
Recapitulatie					601.42	
TOTAL GENERAL					2,233.15	